

**DEPARTMENT OF BUDGET AND MANAGEMENT**

Project ID: DBM12-PB-2021-10-01  
 Project Name: Construction of Multipurpose Covered Area

Location : DEPARTMENT OF BUDGET AND MANAGEMENT RO-12, Barangay Morales, Koronadal City

**BILL OF QUANTITIES**

ITEM	DESCRIPTION	UNIT	QUANTITY	PERCENTAGE 100%	COST			TOTAL
					MATERIAL	LABOR	EQUIPMENT	
<b>OTHER GENERAL REQUIREMENTS</b>								
	Permits and Clearances	l.s	1.00	1.33%				
	Project Billboard / Signboard	each	1.00	0.24%				
	Occupational Safety and Health Program	l.s	1.00	0.63%				
	Mobilization / Demobilization	l.s	1.00	0.68%				
								<b>Sub Total</b>
<b>CIVIL, MECHANICAL, ELECTRICAL AND SANITARY / PLUMBING WORKS</b>								
<b>EARTH WORKS</b>								
	Structure Excavation (Common Soil)	m3	50.14	0.64%				
	Embankment from Structure Excavation	m3	37.77	0.40%				
	Gravel Fill	m3	3.70	0.25%				
								<b>Sub Total</b>
<b>PLAIN AND REINFORCED CONCRETE WORKS</b>								
	Structural Concrete (Class A)	m3	20.00	7.68%				
	Reinforcing Steel (Deformed, Grade 40)	kg	1365.00	6.91%				
	Formworks and Falseworks	l.s	1.00	1.17%				
								<b>Sub Total</b>
<b>FINISHING AND OTHER CIVIL WORKS</b>								
	Fabricated Metal Roofing Accessory (Ridge Roll)	ln.m	26.40	0.63%				
	Fabricated Metal Roofing Accessory (Flashing)	ln.m	34.20	0.81%				
	Fabricated Metal Roofing Accessory (Gutters)	l.s	52.80	1.27%				
	Prepainted Metal Sheets (Rib Type)	m2	452.00	15.79%				
	Cement Plaster Finish	m2	49.00	0.57%				
	Painting Works (Masonry/Concrete)	m2	42.60	0.78%				
	CHB Non Load Bearing (including Reinforcing Steel) - 100mm	m2	16.00	0.71%				
	Structural Steel	l.s	1.00	57.44%				
								<b>Sub Total</b>
<b>WATER SUPPLY</b>								
	PVC Polyvinyl Chloride Pipe	l.s	1.00	2.07%				
								<b>Sub Total</b>
								<b>GRAND TOTAL</b>

Submitted by:

\_\_\_\_\_

Position

\_\_\_\_\_

Date: \_\_\_\_\_